



# SEE testing of the LHC Beam Interlock System



BT/BP/RS AB/CO/MI 6th LHC Radiation Workshop 29<sup>th</sup> November 2007





# Testing the Beam Interlock System



## 1. The Beam Interlock System

- Electrical and Physical Architecture
- Component Locations
- Design for Durability
- Scope of the Tests (CIBD and CIBU)

## 2. Power Supply Tests and Results

- Detailed Description of the Power Supply
- Test methods
- Test Results

## 3. User Interface Tests and Results

- Detailed Description of the User Interface
- Test methods
- Test Results

## 3. Conclusions and Future Focus

- Test Conclusions
- Where do we go from here?



# Testing the Beam Interlock System



## 1. The Beam Interlock System

- Electrical and Physical Architecture
- Component Locations
- Design for Durability
- Scope of the Tests (CIBD and CIBU)

## 2. Power Supply Tests and Results

- Detailed Description of the Power Supply
- Test methods
- Test Results

## 3. User Interface Tests and Results

- Detailed Description of the User Interface
- Test methods
- Test Results

## 3. Conclusions and Future Focus


- Test Conclusions
- Where do we go from here?




# Beam Interlock System Locations




Designed to protect CERN high energy accelerators = SPS / LHC / INJ / EXT






~200 connections to User Systems distributed over 28kms





# Signals



USER SYSTEM rack


“some radiation”

Worst = UJ76-type

In INTERLOCK rack

“negligible radiation”

Typical background at Sea Level



2U Chassis

VME Chassis



1. Critical Function separate (fewer critical circuits)
2. Failure Modes Analysis (weaknesses designed out)
  3. Xilinx CPLD proven (AB/PO)
  4. 5V and redundant PSU (Highly Available)
  5. Mature Electronics (Not risky!)
6. Electro-Magnetic Compatibility (key issue from start)

= robust design reliability and rad tolerance seem linked!

-running  $\frac{1}{4}$  LHC system in SPS for nearly 2 years ☺





# Motivations for the Tests



The Beam Interlock Controller (x17 in LHC)

- few in surface buildings
  - most in zones considered 'negligible radiation'
  - one in control room
  - VME Chassis can be moved to surface if ever there is a problem
  - any problem will result in safe failure by design
- VME is the basis = Not going to Test

The User Interface (x130 in LHC)

- Goes where the User System is "UJ76"
- We have to Test

The User Interface Power Supply (x260 in LHC)


- Goes where the User Interface is "UJ76"
- We have to Test

- accumulated dose? User Systems will have the same problem!
- need to know the limits
- POWER SUPPLY only total dose is interesting


## User Interface



BIC (Front) TT40



BIC (Rear) TT40





# Testing the Beam Interlock System



## 1. The Beam Interlock System

- Electrical and Physical Architecture
- Component Locations
- Design for Durability
- Scope of the Tests (CIBD and CIBU)

## 2. Power Supply Tests and Results

- Detailed Description of the Power Supply
- Test methods
- Test Results

## 3. User Interface Tests and Results

- Detailed Description of the User Interface
- Test methods
- Test Results

## 3. Conclusions and Future Focus

- Test Conclusions
- Where do we go from here?



Tracopower TXL-025-25S  
5V, 5A, 25W

Device housed in shielded conductive case

Reliability analysis = redundant PSU = good Availability

- Decoupling diode added
- +3% trim to accommodate  $V_{\text{diode}}$

5A Fuse added on input

EMC Tests done with CIBU/CIBD configuration

- Very good results

<https://edms.cern.ch/document/762174/>

Not the cheapest, but


Tracopower have a great reputation (AB/PO)


Very complete datasheets





# CIBD – 5A 5V PSU






~12cm

Radiation levels at the electronic rack positions at IR7 (average values for the racks situated on the ground floor). The statistical error is  $\leq 20\%$ .

	Dose (Gy/y)	Hadrons > 20 MeV (cm <sup>-2</sup> /y)	1 MeVeq. flux (cm <sup>-2</sup> /y)
UJ76	0.5	$8 \cdot 10^8$	$2 \cdot 10^9$
RR73/77	0.3	$1 \cdot 10^8$	$6 \cdot 10^8$



PROSPERO

235U core and a 238U reflector  
“Displacement Damage Test”

NEUTRONS

Energy = 1MeV

Fluence = 1E12 n/cm<sup>2</sup>

=Several 10's Years LHC

<1% Voltage change

And CIBU OK down to 4.5V

(guaranteed by design)

PSU well protected -

PSU 25W, we need <5W

Degradation is expected & planned for



# Testing the Beam Interlock System



## 1. The Beam Interlock System

- Electrical and Physical Architecture
- Component Locations
- Design for Durability
- Scope of the Tests (CIBD and CIBU)

## 2. Power Supply Tests and Results

- Detailed Description of the Power Supply
- Test methods
- Test Results

## 3. User Interface Tests and Results

- Detailed Description of the User Interface
- Test methods
- Test Results

## 3. Conclusions and Future Focus

- Test Conclusions
- Where do we go from here?





# User Interface Specification



Device housed in conductive case with Burndy Connectors

- great EMC

- good reliability from connectors (AB/PO already use these)

Completely 5V

- good reliability (more resistance to perturbation)

Classic 7400 Series

- mature technology

- wide support

Current Loop inputs

- accommodate many different types of User System

- DESY input circuit (M. Werner)

RS485 Outputs

- Good integrity

- Mature Technology

9500 Xilinx CPLD for TEST and MONITOR

- Manchester frames (Used General Machine Timing as a basis)

- excellent dependability (AB/PO already use these)

- Not susceptible to program corruption


100% remotely testable


100% remotely monitorable



# User Interface









Projet/ Project	CIBU		NAME	TEL	DATE
Ensemble/ Set	Controls Interlocks Beam User (CIBU) 2005		Resp	BMT	1 Jan 2006
Sous-ensemble/ Underaset	SILK TOP	File EXT : SET	Designer	BMT	
	Drawing Number	EDMS	Drawn by	Martin Christophe	
	CIBU 3v1	LHC	MDDA		
			MDOB		
	LABORATOIRE EUROPEEN POUR LA PHYSIQUE DES PARTICULES EUROPEAN LABORATORY FOR PARTICLE PHYSICS GENEVE / GENEVA	ECHELLE/ SCALE	1/1	INDICE	

## Beam-2

## Beam-1



Projet/ Project	CIBU		NAME	TEL	DATE
Ensemble/ Set	Controls Interlocks Beam User (CIBU) 2005		Resp	BMT	1 Jan 2006
Sous-ensemble/ Underaset	SILK TOP	File EXT : SET	Designer	BMT	
 Drawing Number <b>CIBU 3v1</b>	EDMS	LHC	Drawn by	Martin Christophe	
	LABORATOIRE EUROPEEN POUR LA PHYSIQUE DES PARTICULES EUROPEAN LABORATORY FOR PARTICLE PHYSICS GENEVE / GENEVA		MOA		
	ECHELLE/ SCALE	1/1	MOB		INDICE




Projet/ Project	CIBU		NAME	TEL	DATE
Ensemble/ Set	Controls Interlocks Beam User (CIBU) 2005		Resp	BMT	1 Jan 2006
Sous-ensemble/ Underasst	SILK TOP	File EXT : SET	Designer	BMT	
 AB/CO/IN	Drawing Number	EDMS	Drawn by	Martin Christophe	
	CIBU 3v1		MDDA		
LABORATOIRE EUROPEEN POUR LA PHYSIQUE DES PARTICULES EUROPEAN LABORATORY FOR PARTICLE PHYSICS GENEVE / GENEVA		ECHELLE/ SCALE	1/1		INDICE






# Test Areas



Projet/ Project	CIBU		NAME	TEL	DATE
Ensemble/ Set	Controls Interlocks Beam User (CIBU) 2005		Resp	BMT	1 Jan 2006
Sous-ensemble/ Under-set	SILK TOP	File EXT : SET	Designer	BMT	
 AB/CO/IN	Drawing Number	CIBU 3v1	EDMS	LHC	
	LABORATOIRE EUROPEEN POUR LA PHYSIQUE DES PARTICULES EUROPEAN LABORATORY FOR PARTICLE PHYSICS GENEVE / GENEVA		ECHELLE/ SCALE	1/1	INDICE

All use the SAME electronic circuit! It's repeated four times




Projet/ Project	CIBU		NAME	TEL	DATE
Ensemble/ Set	Controls Interlocks Beam User (CIBU) 2005		Resp	BMT	1 Jan 2006
Sous-ensemble/ Under-set	SILK TOP	File EXT : SET	Designer	Martin Christophe	
 AB/CO/IN	Drawing Number	CIBU 3v1	MDDA		
	EDMS		MDOB		
LABORATOIRE EUROPEEN POUR LA PHYSIQUE DES PARTICULES EUROPEAN LABORATORY FOR PARTICLE PHYSICS GENEVE / GENEVA		ECHELLE/ SCALE	1/1	INDICE	




The mission critical function for the CIBU;

-relay USER\_PERMIT correctly

Nothing else! All the BLACK lines are critical!



The mission critical function for the CIBU;  
-relay USER\_PERMIT correctly






# Test Sequence During Irradiation



5 steps, every two seconds we move to the next step, then repeat...

We MEASURE all board current consumptions!

PERMIT A [mA] ... PERMIT B [mA] ... CIBU [mA]






# Test Sequence During Irradiation



5 steps, every two seconds we move to the next step, then repeat...

## 1. Cycle USER PERMIT A






# Test Sequence During Irradiation



5 steps, every two seconds we move to the next step, then repeat...

1. Cycle USER PERMIT A
2. Cycle USER PERMIT B






# Test Sequence During Irradiation




5 steps, every two seconds we move to the next step, then repeat...

1. Cycle USER PERMIT A
2. Cycle USER PERMIT B
3. Cycle BEAM PERMIT INFO




5 steps, every two seconds we move to the next step, then repeat...

1. Cycle USER PERMIT A
2. Cycle USER PERMIT B
3. Cycle BEAM PERMIT INFO
4. Internal TEST PERMIT A




5 steps, every two seconds we move to the next step, then repeat...

1. Cycle USER PERMIT A
2. Cycle USER PERMIT B
3. Cycle BEAM PERMIT INFO
4. Internal TEST PERMIT A
5. Internal TEST PERMIT B





1. USER\_PERMIT Optocoupler
2. USER PERMIT Current Regulation Circuit
3. USER PERMIT RS485 Driver
4. USER PERMIT Schmidt Trigger
5. The WHOLE CIBU





## Irradiation Parameters

60MeV Protons – OPTIS at PSI


15MeV/cm<sup>2</sup>/mg in SiO<sub>2</sub> – can cause SEE in plastic packages

N.B. 1 x 10<sup>11</sup> protons cm<sup>-2</sup> equivalent to 140 Gy

“Representative of LHC Environment” – F. Faccio, M. Muhtinen

Radiation levels at the electronic rack positions at IR7 (average values for the racks situated on the ground floor). The statistical error is  $\leq 20\%$ .

	Dose (Gy/y)	Hadrons > 20 MeV (cm <sup>-2</sup> /y)	1 MeVeq. flux (cm <sup>-2</sup> /y)
UJ76	0.5	$8 \cdot 10^8$	$2 \cdot 10^9$
RR73/77	0.3	$1 \cdot 10^8$	$6 \cdot 10^8$





# Test 1 – The Optocoupler




Received a TOTAL DOSE of 62 Gy =  $4.8 \times 10^{10}$  pcm<sup>-2</sup>

10 Glitches observed – observation window open only ¼ of test - 40 assumed.

Cross Section =  $8.3 \times 10^{-10}$  for Optocoupler Glitches

Test 1: User Permit Glitches versus Total Dose





# Test 1 – The Optocoupler




usual transition times were observed during the test

~3.6us delay for TRUE to FALSE

~0.6us delay for FALSE to TRUE

Test 1: User Permit Transition Time versus Total Dose





# Test 2 – The Current Regulator




Received a TOTAL DOSE of about 120 Gy

NO Glitches observed

Current regulation drifted by about 4%

Test 2: User Permit Current Regulation versus Total Dose





# Test 3 – RS485 Driver




Received a TOTAL DOSE of 496 Gy

NO Glitches observed, No FALSE Transitions

FAILED SAFE at 496 Gy, power cycle restored operation

Test 3: User Permit Transition Time Versus Total Dose






# Test 4 – Schmidt Trigger



Received a TOTAL DOSE of 1000 Gy (then experiment halted)

NO Glitches observed, NO FALSE transitions

Test 4: User Permit Transition Time versus Total Dose








# Test 5 – Whole PCB



Two PCBs tested

~140-160Gy - CPLD stopped sending data frames

Monitor Communications Failures versus Total Dose






# Overall Current Consumption



Three PCBs tested at various points

User Interface ID 1 = 180 Gy

User Interface ID:1 Current Consumption Versus Total Dose






# Overall Current Consumption



Three PCBs tested at various points

User Interface ID 682 = 1650 Gy

User Interface ID:682 Current Consumption versus Total Dose






# Overall Current Consumption



Three PCBs tested at various points

User Interface ID 2 = 160 Gy

User Interface ID:2 Current Consumption versus Total Dose





# Testing the Beam Interlock System



## 1. The Beam Interlock System

- Electrical and Physical Architecture
- Component Locations
- Design for Durability
- Scope of the Tests (CIBD and CIBU)

## 2. Power Supply Tests and Results

- Detailed Description of the Power Supply
- Test methods
- Test Results

## 3. User Interface Tests and Results

- Detailed Description of the User Interface
- Test methods
- Test Results

## 3. Conclusions and Future Focus

- Test Conclusions
- Where do we go from here?



## Critical Path of Beam Interlock System

- $8.3 \times 10^{-10}$  Cross-Section for Glitches = use 1.6us GLITCH FILTER!
  - Good radiation tolerance
  - CPLD failed first at 150Gy – only for MONITORING
- BUT once we got it back here – reprogrammed it and it worked!
- Will monitor Glitch counters to indicate potential problems


Have plans for RAD HARD CIBU but they're on hold

- Needs motivation, time and money! (\$)
  - VME is weak? move BICs to 'surface' (\$\$\$)
- Critical Matrix CPLD is same as in CIBU (3.3V variant)
  - VME PSU – redundant!

Have researched a RAD HARD BIC (not including VME)  
Needs motivation, time and lots of money (\$\$\$\$\$)



# USER\_PERMIT SEE Glitch Filter




USER\_PERMIT

BEAM\_PERMIT

If USER\_PERMIT FALSE for  $\leq 1.6\mu\text{s}$  then it's IGNORED!

= NO BEAM ABORT



If USER\_PERMIT FALSE for  $> 1.6\mu\text{s}$  then it's ACCEPTED!

= BEAM ABORT



# Closing remarks



- it was a LOT of effort to get the tests organised
- Thanks to Thijs Wijnands / Christophe Martin et al. for all the great work
  - additional tests won't need as much effort
- after LHC beam commissioning started – we could do some more!
  - If we feel it's necessary:

Optical Transmission Board... (CIBO)

Fibre Extended User Interface (CIBFU/CIBFC)

VME Equipment (find the weaknesses?)

We should plan some beam time next year. NOT a priority for LHC

“Better the devil you know”





FIN



# Tracopower TXL-025-25S



Hold-up time 20 ms min.

**INPUT VOLTAGE fails or glitches = OUTPUT VOLTAGE maintained**

Reliability /calculated MTBF (MIL-HDBK-217F) >250'000 h @ 25 °C typ.

**Mean Time Between Failures = several years**

Electromagnetic compatibility (EMC), Emissions	<ul style="list-style-type: none"> <li>- Conducted input RI suppression</li> <li>- Harmonic current emissions</li> <li>- Flicker</li> </ul>	EN 55022, class B, FCC part 15, level B IEC/EN 61000-3-2, class D (TXL 120/150/220) IEC/EN 61000-3-2, class A (others) IEC/EN 61000-3-3
--	---	--

Electromagnetic compatibility (EMC), Immunity	<ul style="list-style-type: none"> <li>- Electrostatic discharge ESD</li> <li>- RF field immunity</li> <li>- Electrical fast transients/burst immunity</li> <li>- Surge</li> <li>- Conducted RF</li> <li>- Magnetic field</li> <li>- Voltage dip</li> </ul>	IEC/EN 61000-4-2 4 kV / 8 kV IEC/EN 61000-4-3 3 V/m IEC/EN 61000-4-4 1 kV IEC/EN 61000-4-5 1 kV / 2 kV IEC/EN 61000-4-6 3 V/m IEC/EN 61000-4-8 3 A/m IEC/EN 61000-4-11
---	---	--

Safety standards UL 60950-1, IEC 60950-1, EN 60950-1

Safety approval cUL/UL File E188913

**Industrial Device = heavily tested, good conformity**

**Short Circuit and Over Voltage Protected**

**Three Year Guarantee**



<http://indico.cern.ch/conferenceDisplay.py?confId=20366>

<http://doc.cern.ch/archive/electronic/cern/others/LHB/public/lhcb-2003-049.pdf>

<http://doc.cern.ch/archive/cernrep/2007/2007-001/p547.pdf>

<http://doc.cern.ch/archive/electronic/cern/others/LHC/Note/project-note-385.pdf>