


LHC Cryogenics in UX85 and Strategy against radiations

S. Claudet, LHC cryogenics

LHC Radiation days, 29-30Nov'07






Content

- Introduction
- Specificities of UX85 cavern
- Impacts on cryo related components
- Proposed actions and status
- Summary





Introduction to LHC Cryogenics (1/3)





Introduction to LHC Cryogenics (2/3)




Mostly sub-systems with COTS instrumentation


Special case

Radiation as engineering constraints

Legend



QSC_(A,B,C): Warm Compressor Station
 QSR_(A,B): Surface 4.5 K Refrigerator Cold Box
 QURA: Underground 4.5 K Refrigerator Cold Box
 QURC: 1.8 K Refrigeration Unit Cold Box
 QUI_(A,B,C): Cryogenic Interconnection Box



Green box: Commissioned & accepted

Red box: Delivered / Under installation

Orange box: Ordered (Contract placed)





Pink box: Under commissioning

Blue box: Under fabrication

Yellow box: Under definition



Introduction to LHC Cryogenics (3/3)




S. Claudet - 29 Nov'07



Machine interface:
From Rad-Hard sensors to
Rad-Tol electronics in
sheltered areas




LHC Cryo in UX85 - 6th Radiation days





Content

- Introduction
- Specificities of UX85 cavern
- Impacts on cryo related components
- Proposed actions and status
- Summary






LHCb – detector area




J. Christiansen



UX85: Simulated doses for single events




(C. Theis & co-workers, EDMS 735075)



Complete technical assessment of the problem can be found in TS note 2006-001 LEA by A-L Perrot (EDMS 695442)




UX85 Cryogenics Installation



Radiation sensitive devices

Level 1



NB: all measures are in cm

Point 1



DP/PA couplers and links (Siemens)



PLCs Schneider (Modicon)



High frequency converters, Magnetic level controllers.



Thyristors




PLCs Siemens S7-300




Electro-pneumatic valves positioners

Frequent stops could be due to single events !!!



Content


- Introduction
- Specificities of UX85 cavern
- Impacts on cryo related components
- Proposed actions and status
- Summary



Proposed actions

endorsed by LHC project leader's office

CERN
CH-1211 Geneva 23
Switzerland



the
**Large
Hadron
Collider**
project

LHC Project Document No.

LHC-QI-EC-0007

EDMS Document No.

819444

Engineering Change requested by (Name & Div./Grp.) :

T.Wijnands, S.Claudet

Date: 2007-03-05

Engineering Change Order – Class I

Radiation tolerance of the cryogenic installation in UX85

Brief description of the proposed change(s) :

To improve the radiation tolerance of the cryogenics installation in UX85 with the LHC baseline by relocating the industrial controls equipment to UL84 (stage I) and to equip the QUI and the QURC in UX85 with electro-pneumatic valve positioners with remote electronics (stage II) equally located in UL84. This will give an operational safety with regard to radiation effects in line with that of the LHC baseline.


Equipment concerned :

**QUI in UX85
QURC in UX85**

Drawings concerned :

**LHCLJ8US0019
LHCJUX850004**

Documents concerned :



Sequence of actions to be taken

(considering sensitivity of components and possible effects)

Phase 1:

Displacement of Cabinets for Cold Compressor magnetic bearings, PLCs and Profibus cards

Halogen free cables for CC magnetic bearing:	90'000 CHF
Cabinets for PLC's, Profibus, cabling (QUI):	30'000 CHF
Cabinets for PLC's, Profibus, cabling (QURC):	50'000 CHF
Supporting frame, handling:	10'000 CHF
Total Phase 1:	180'000 CHF


Phase 2:

Remote valve positioners

Supply & Installation of digital positioners (QUI):	90'000 CHF
Supply & Installation of digital positioners (QURC):	60'000 CHF
Supporting frame, handling:	10'000 CHF
Total Phase 2:	160'000 CHF


The delay for the supply of hardware like special cables is at least six months. With the present LHC schedule, the earliest implementation of phase 1 could be second half of 2007 after the hardware commissioning of Point 8.

UX85 Cryogenics Installation



Radiation sensitive devices

Level 1



NB: all measures are in cm

Point 1



High frequency converters,
Magnetic level controllers.




Thyristors




PLCs Siemens S7-300

A-L Perrot



DP/PA couplers and links
(Siemens)





PLCs Schneider (Modicon)




Electro-pneumatic
valves positioners



UX85: Simulated doses for single events





Safer zone,
fluence reduced
by about 200



Hadron fluence ($E > 20$ MeV) [cm^{-2}] at the beam level (floor 0) after 10 years of LHC operation. A safety factor of 2 was included in the normalization.




Integration study





Timing of actions to be taken




Proposed approach:

- Phase 1: Before collisions at high luminosity, remove the most sensitive equipment like PLC's, DP/PA couplers, controllers for cold compressor magnetic bearings. A proposal was integrated in UL84.
- Phase 2: Based upon monitoring and operating experience, digital valve positioners with remote electronics could be installed.

- Long delivery items have been ordered last summer, delivery Jan'08
- Project for electrical cabinets remote PLC's to be launched
- Implementation as foreseen after hardware commissioning of P8

The modifications proposed above will reduce the risk of radiation induced failures in cryogenic equipment in UX85 to a level comparable to that of cryogenic equipment in the tunnel.



Summary

- Follow standard procedure (as we did for all other areas with similar problems)
- Complete technical assessment of the problem can be found in TS note 2006-001 LEA by A-L Perrot (EDMS 695442)
- We take reasonable precautions where we know there will be a problem :
 - Most sensitive components to be treated before LHC collisions at moderate energy (long delivery items ordered)
 - Radiation monitoring system in UX85 and US85 is in place & operational to assess real situation
 - For the cold compressors (critical elements of QURCS) no solution exist but fallback solutions will be prepared in case we need them

Thanks to A-L. Perrot, T. Wijnands and P. Proudlock for help and support