

Detector Construction, QC & Commissioning

issues for a Supercollider

remarks and personal views based on experience and plans from LHC experiments
(ATLAS and CMS) and from the studies for LHC upgrades

Supercollider experiments: generalities & themes for this presentation

Trends affecting detector construction

Integration


QA/QC and project monitoring

Commissioning

Conclusion

Supercollider experiments

high energy, high luminosity



-are big, few in number and costly
-risks are large, failure unthinkable

-involve many : countries
funding agencies
institutes
physicists

and need a large, well-equipped
host organisation

timescale long: obsolescence built-in

experimental environment is hostile
special components
difficult maintenance
difficult disposal

collision rate & stored data volume are
challenging

Trends affecting detector construction

sensor technologies : other talks this workshop

sociology

administrative & legal constraints

size of experiments :

industrial production

reception areas

custom detector manufacturing: automation & hand-building.

logistics

electronics

Sociological constraints

- **Supercollider projects take 10 years or more to build before operation**

- subject to several rounds of national and international economic and political cycles
unwise to plan based on the good times

- overlap with comparable running experiments is reducing
timescale too long for Ph.D students to see final data

- human lifetime & fragility become non-negligible factors
more people burn-out, move on or stagnate
attrition of expertise between design , construction and operation
start experiments with few personnel experienced in commissioning
maintenance workers less willing to suffer mSv radiation doses?


- **important to create opportunities for young people (from many fields) to contribute part of their careers in a satisfying way.**

Management and Communication

semi-academic heirachy in a collaboration is intrinsically (and usually beneficially) weak...

social complexity increases combinatorially $n(n-1)/2$

... where n might be # institutes, teams, funding agencies, review committees..etc



management theory of limited use- **must still rely on the drive of physicists to get at physics**

Administrative & Legal constraints

an increasingly regulated, accounts-driven world is becoming more hostile for research-type activities without an immediate economic objective and involving maxima & minima of construction activity

Host lab resources, diversity and expertise in both R & D and construction support reducing

Legal/practical restrictions are increasing on: staff mobility from institute to institute
hiring of temporary staff

Labour from developing economies will get less and less cheap and is not a long-term solution

Project financing is tending more and more towards P + M

more flexibility and easier accountability (in a open and de-regulated economy)
materials/personnel/travel/contingency etc all paid from budget
reduced or absent underlying infrastructure and permanent staff in institutes

Risk of inadequate continuity in the technical knowledge base

Administrative and Legal constraints

- **Tolerance for negative environmental impact is reducing (good thing!)**

HEP is generally not a polluting activity, but is affected (costs,time) for instance by:
restrictions on tunneling activities & surface infrastructure
restrictions on emissions (eg effluent detector gases) and contamination
requirements on traceability of waste and disposal methods(esp radioactive)
reduction in allowed radiation dose rates for workers

- **Equipment has to follow codes for industrial scale, permanent objects eg seismic stability**

- **Access to the latest microelectronic technologies is restricted.**

all the above constrain the design, construction, commissioning and operation of research facilities

(Note in passing: A supercollider project must take increasing care to avoid being classified with the nuclear industry in the minds of bureaucrats or of the public)

Industry can make large objects increasingly precisely

application of numerically control to large machine-tools *200 μ m precision on these holes*



disk diameter 14m

but transport to experiment site sets limits

CMS inner vacuum vessel, Jura



and transport surprises are quite frequent...


& expensive....

$\frac{1}{2}$ ATLAS endcap magnetic vacuum vessel, Jura



back-up resources need to be industrial scale

ATLAS Barrel Toroid Integration and Test



industry can
default due to

unattainable spec

unprofitability

economic cycle
effects


etc

→ quite common
in LHC projects

and reception/pre-integration areas large



Automation



“robots” increasingly applied to precise repetitive tasks with precision components

- adapting components to robot is non-trivial
- mistakes are also made the same every time!



Manual assembly still needed...



nimble hands sometimes better custom robots

CMS forward calorimeter

600k quartz fibres inserted in absorber modules by hand in ~15 months.



Logistics

ideal world:

processes should be concentrated on one site or a small number of parallel sites

lines of communication shorter, responsibility clearer, uniform quality easier to maintain

ie input : procured materials <--> output: tested detectors

centres should be able to back each other up ie manufacture interchangeable between centres

number of different variants of a part should be minimised

“few specials” to fill acceptance hole can cost same design & prototyping effort as “standards”


in eg LEP collaborations, many sub-systems were still the prime responsibility of one institute

unfortunately, the nature of supercollider collaborations and their sociology

tends towards distributed production, and even distributed processes:

- needed to maintain institute infrastructure, intellectual attraction and distribute expertise...

the logistic price of this must be factored in, not overlooked!!



CMS TK 2003

Logistics: transport carries risks

however careful the handling.... accidents *will* happen to both big and small packages...



assess risks correctly, insure where appropriate



Electronics: 40% of cost, 90% of risk?

high collision rate → high current per electronic channel

high precision tracking & calorimetry → high channel count

high radiation environment → rad tolerance needed.(qualified COTS or custom-made)

electronics tasks were poorly represented in LHC experiment high level planning before mechanical manufacturing of detection systems was launched subsequently on-detector electronics tasks suddenly appeared on critical path!!

usually due to

- : underestimation of engineering resources
- : over-dependence on a very few key individuals
- : failed/poor yield submissions
- : rad tolerance testing taking unforeseen time
- : vulnerability to foundry delivery schedules
- : vulnerability to technologies disappearing or changing
- : single batch ordering incompatible with funding profiles

much electronics has been retrofitted to mechanically completed detectors → risk

→ schedule pressure → burn-in treated as a contingency → pay the price later?

Electronics experience

Arrival of “final” electronics

+ serious consideration of services —> mechanical integration “zombies”,
(cables, connectors, power distribution etc)

final system tests generally done late—> bad surprises coming late?

eg EMC and grounding issues.

Power density and cooling challenges of supercollider detectors are outside our previous experience and can be expected to give problems!


Power consumption of ATLAS/CMS on-detector equipment is of order 1.0 MW

Maintenance tools: rate of update, backward compatibility, obsolescence
issues underestimated

Electronics

**Moore's law is still good for processor power
but need not apply to other components**

eg CMS ECAL front end electronics



before $0.25\mu\text{m}$ technology (fast, rad-hard data reduction on detector) was proven design minimised the risk from on-detector rad-hard components by shipping data from individual channels off-detector.

this design bet on a the plausible, but large, reduction (x5) in the cost of optical links ...which never occurred (capacity of single fibres was nowhere near saturated).

(luckily the success of $0.25\mu\text{m}$ and the motivation of the teams working with it seem to have saved the day)

Electronics: the future

0.25 μm a success at LHC!

yield, noise, power consumption,
rad tolerance at reasonable cost
more signal processing on detector

represents the fruits of a long collaboration with IBM

progression will probably be $\rightarrow 0.13\mu\text{m} \rightarrow 0.065\mu\text{m}$. (x 16 more gates per unit chip size)

rad tolerance should be good (at least of $0.13\mu\text{m}$ with SiO_2 dielectric)

overcome any SEU effects by redundancy of key elements

refresh from local flash memory

Research collaboration with big vendors for our special requirements works!

but we represent a tiny market (IBM makes 40k $0.25\mu\text{m}$ wafers a week)...start early!

-experience suggest processes are stable when number of wafers made is large (say $>10\text{k}$)


Optical links:

expect progression from 1.6 Gbit (now) \rightarrow 10 Gbit (straightforward) \rightarrow 10Gbit
through mono-mode fibre to avoid dispersion

System design (across whole expt) is better as an input than an afterthought

Electronics: proliferation of FPGAs

- **Complex 9U digital board**
 - optical signal deserialiser
 - data digitisation
 - data reduction
 - cluster (hit) finding
 - calibration
 - synchronisation
 - data assembly and transmission
- **mostly empty space!**
...relies on FPGAs:




increasingly, DAQ functions are downloaded to FPGAs on- and off-detector
-requirements and cross-checks on algorithms are ~ as strict as for ASICS
-platforms to program FPGA's subject to obsolescence?

Engineering Integration

a thankless but vital task, needing a dedicated team and resources



eg Joint CERN-ETHZ project: supporting CMS Technical Coordination since 1997



Integration Coordinator + 3-4 CAD draughtsmen/engineers, QA/QC engineer
tasks: parameter envelopes, change control, non-conformities
tools: 3-D modelling : translation from multiple external CAD systems, CDD, EDMS.
: full scale sectional model in bldg 867.
centre: focus for detailed mech. engineering links between subsystems (link meetings)
temporary facilities for collaborating groups.

Integration: Cabling modelling

ATLAS ID services



1:1 models still essential in verifying layouts & making reality check with drawings and 3-D CAD.

Integration: cable procurement & installation

Subsystem/function cells could be not always correct because different cables of the same type could be joined in one row

LARG

Some of the listed cables needs to be installed together with cryogenic services: then installation starts earlier, 19.02.2004
 ALL = EM Barrel SideA & SideC+ END-CAP Side A & Side C (EMB, EMEC, HEC, FCAL)

detector	subsystem	function	type	diame	N of c	Len, Km	reference	connector	connector	characteris	comment	2002			2003				2004																				
												Se	Oc	No	De	Jan	Feb	Mar	Apr	May	Jun	Jul	Au	Se	Oc	No	De	Jan	Feb	Mar	Apr	May	Jun	Jul	Au	Se	Oc	No	De
LArg	All	Trigger Cal	Electrical	12.50	374	39.38					16 shielded	Must go th	Cables have been already ordered																										
LArg	All	High Volta	HV	13.00	156	21.54					25 + 2 spare	-			10														20			20							
LArg	All	Low Volta	LV	13.00	66	5.08					-	-					20												20		20								
LArg	All	Data and S	Optical	9.50	58	4.35	Ericsson C	12-way parallel optical			This is a cus	The cable																	20		20								
LArg	All	Monitoring	Electrical	20.00	74	5.31						Detector t																		20		20							
LArg	All	TTC Optical	Optical	3.00	244	16.38					Individual fibe	Must go th																				20		20					

Please note that TTC optical fibers should be part of Level 1 Trigger

These cables must be installed together with the cryo services

PRR1 completed. Cable and connectors are CERN Stock Items

The optical fibres already passed PRR1 almost a year ago. However length was never specified, will be important to have a length approximation in January 2003

Tendering := PRR1 (Length with 20% accuracy, verification of CERN safety)

Contract = PRR2 (Precise length)

Last acceptable day for delivery to CERN

Beginning of installation

tends to get neglected as unglamorous, by both detector & electronics specialists
 → easily comes on to critical path. Plan must include maintenance as well as installation

Quality Assurance/control

Quality assurance:

the set of planned and systematic activities which ensure that the experiment project:

- attains the required performance

- is completed and running on time

- complies with legal and other rules and regulations

- is safe, reliable and maintainable



applies everywhere from design through prototyping, production, assembly & installation

includes well known concepts such as part identification, documentation, traceability, change control, peer review, scheduling & reporting, inspection & test (QC).

most of the activities are obviously needed, and were always done but....

Quality Assurance/Control

As collaboration size has grown, that which used to be done intuitively needs to become somewhat more formal....some differences of opinion on how formal...


		QUALITY ASSURANCE POLICY QAP CONTENTS & STATUS	
ATLAS Project Document No. Project - System - Institute - Type - Sequential No.	Institute Document No.	Created	Page
ATL-GE-CERN-QAP-0100.00	CERN / QAP / 100.00	15-Nov-1996	3 of 6
		Modified	Rev. No.
		15-Nov-1996	1.0

<i>Table of Contents</i>	
1. NORMS & REFERENCES.....	4
1.1 NORMS, STANDARDS & GENERAL REFERENCES.....	4
1.2 REFERENCED ATLAS DOCUMENTS.....	4
2. PURPOSE.....	4
3. SCOPE.....	4
4. QAP CONTENT & STATUS.....	4

define rules, guidelines & procedures:

- introduce formalism only where it helps to improve the end result in the HEP environment
- still rely on, and encourage, the motivation of physicists to make a good detector

Engineering data & document management



important for

- document organisation
- reliable archiving
- approval/ change control

- documenting important non-conformities and their resolution

CERN EDMS:took some time to customize for experiments

- now vital
- still cumbersome
- can legitimise falsehoods & obsolete information

Review process

ALL experiments have adopted a similar sequence of project review designed to minimise risks in performance, cost and schedule:

for CMS:

preliminary design review or workshop


intermediate design review or workshop

engineering or final design review (s) → authorisation to procure or manufacture

(committee include reps of all interfacing systems + external experts)

manufacturing progress review (including cost-to-complete)

for pragmatism, items which largely factorise from the system design, can be authorised by smaller scale procurement readiness reviews




CMS reviews 2001

-note concentration in mid- & end-year!

Sophisticated test-rigs

CMS crystal measuring “ACCOS”




ATLAS MDT tomograph



Sophisticated QC devices needed to make repeatable precise tests on large numbers of items. Development/adaption takes time. Can become single-point failures. Some measurements contribute to first pass calibration of detector. -link to database

Construction database & process control

Detector Construction Management & Quality Control Tool



The C.R.I.S.T.A.L. project

Cooperative Repositories & Information System for Tracking Assembly Lifecycle)
CERN, INFN, KFKI, LAPP, UWE

vital for CMS ECAL

application elsewhere proved elusive

- considerable resources are spent on developing tools which manage the construction process, maintain construction databases and facilitate data carry-over into operations.

- a customized central data-base system is needed and works well for individual complex detectors esp where detailed construction data carry forward into calibration.


but

- differences in requirements usually too extreme for a generic system to work experiment-wide. (exc apparently worked for ALICE)


- central process control can contradict the distributed initiative needed to maintain uniform standards. except if central resources are overwhelming.

(IKEA kit model!)


Process flow & QC: eg CMS Tracker modules




Quick test hybrid




Gantry makes modules



Quick test unbonded module




Thermal cycle module



Bonded module test



Wirebond



Final pinhole test


Hybrids: tested ~10 times for ~80h, warm & cold
Modules: tested ~7 times for ~80h, warm & cold
standard procedures, dedicated database, cross checks
between centres.

...watch for choke points & single-point failures!



Survey

Advanced techniques like photogrammetry needed as part of acceptance QC checks at manufacturer as well as after final assembly.

Data carry through into start-up calibration



Equipment Management Database



Locations

- Geometrical position
- Shape
- Parent/children
- Connected cable
- ...


Parts

(Detectors, Racks, electronic boards, cables, etc., including spares)

- Location history for asset tracking / INB
- Specific parameters



User authentication



DB data handler (procedures)



Logbook





Bar code reader

Rack Wizard

Graphical user interface


Web front end

Cable Labels View



Label printer

Project planning and monitoring



- overall timeframes set by
accelerator start-up date
critical sequences
resource loading
- efficient progression towards
completion requires a plan
and
with increasing tendency to
P+M accounting in sub-projects
idle time becomes very costly
(standing/marching army)

“Einstein discovers that time is actually money” - Gary Larson

Summary schedules

approx the same process for ATLAS/CMS

ID	Name	Start	Finish	2003	2004	2005	2006	2007	2008
1	PHASE 1: Infrastructure	4 Apr '03	24 Sep '04	PHASE 1: Infrastructure					
2	Experiment Surface building SX1	15 Apr '03	16 Feb '04	Experiment Surface building SX1					
22	Pit PX14	30 Jun '03	24 Nov '03	Pit PX14					
28	UX 15 Hand-over	12 May '03	12 May '04	UX 15 Hand-over					
29	Experimental Cavern UX15	4 Apr '03	24 Sep '04	Experimental Cavern UX15					
135	PHASE 2: Barrel Toroid & Barrel Calorimeter	18 Sep '03	9 Mar '06	PHASE 2: Barrel Toroid & Barrel Calorimeter					
136	Phase 2a: ATLAS Bedplates and Feet	18 Sep '03	6 Jan '04	Phase 2a: ATLAS Bedplates and Feet					
144	Phase 2b: Barrel Toroid	7 Jan '04	17 May '04	Phase 2b: Barrel Toroid					
422	Phase 2c: Barrel Calorimeter	20 Feb '04	9 Mar '05	Phase 2c: Barrel Calorimeter					
640	Phase 2d: Racks, Pipes & Cables	13 May '04	22 Apr '05	Phase 2d: Racks, Pipes & Cables					
704	PHASE 3: End-cap Calorimeters & Muon Chambers	6 Dec '04	12 Apr '06	PHASE 3: End-cap Calorimeters & Muon Chambers					
705	Phase 3a: Pipes & Cables	6 Dec '04	27 Oct '05	Phase 3a: Pipes & Cables					
803	Phase 3b: Endcap Calorimeter C	13 Dec '04	2 Nov '05	Phase 3b: Endcap Calorimeter C					
923	Phase 3c: Muon Barrel	21 Feb '05	28 Sep '05	Phase 3c: Muon Barrel					
984	Phase 3d: Endcap Calorimeter A	23 May '05	12 Apr '06	Phase 3d: Endcap Calorimeter A					
1118	PHASE 4: Big Wheels & Inner Detector	2 Aug '05	31 Aug '06	PHASE 4: Big Wheels & Inner Detector					
1119	Phase 4a: Big Wheels	2 Aug '05	31 Aug '06	Phase 4a: Big Wheels					
1337	Phase 4b: Inner Detector	28 Sep '05	8 Jun '06	Phase 4b: Inner Detector					
1379	PHASE 5: End-Cap Toroid & Small Wheels	28 Nov '05	17 Jul '06	PHASE 5: End-Cap Toroid & Small Wheels					
1380	Phase 5a: Endcap Toroid	28 Nov '05	17 Jul '06	Phase 5a: Endcap Toroid					
1464	Phase 5b: Small Wheels	18 Apr '06	2 Jun '06	Phase 5b: Small Wheels					
1489	PHASE 6: Beam Vacuum, End wall Chambers	1 Jun '06	14 Aug '06	PHASE 6: Beam Vacuum, End wall Chambers					
1490	Phase 6a: Completion of the Beam Vacuum	1 Jun '06	5 Jul '06	Phase 6a: Completion of the Beam Vacuum					
1532	Phase 6b: End wall Chambers (EO)	23 Jun '06	24 Jul '06	Phase 6b: End wall Chambers (EO)					
1557	Phase 6c: Shielding & full Magnet Test	20 Jun '06	14 Aug '06	Phase 6c: Shielding & full Magnet Test					
1580	Global Commissioning	15 Aug '06	23 Oct '06	Global Commissioning					
1581	Cosmic tests	24 Oct '06	18 Dec '06	Cosmic tests					
1582	ATLAS Ready For Beam	18 Dec '06	18 Dec '06	ATLAS Ready For Beam					


- top down structure
- “ready-for installation” milestones link sub-detector schedules to the master plan
- task-bars linked to expanded schedules and work-packages
- project milestones linked to task completion
- resource loading (at least as a reality check)

ATLAS Installation v 6.12

only significant difference in schedule definition and monitoring of different experiments is the extent to which “work-package” formalism is applied




Installation Manpower in UX15 (excl contractors)

Total Manpower - All phases




Cumulative production charts

CMS CSC electronics




ATLAS MDT work-packages




probably the most useful and motivating project monitoring tool for on-time delivery even though the planning curves are hardly ever reproduced

care needed not to forget to monitor non-glamorous ancilliary or off-the shelf items.

Project progress & cost monitoring



- Money is getting tighter and more project based.
- There is pressure to monitor progress using techniques like: “Earned Value Management” familiar to our U.S. colleagues



- track: work completed
time taken
costs incurred
regularly against a baseline planning
- Effective for comprehensive P+M funding
provided the input data correspond to reality
but needs a large admin staff (~1/30 ratio?)
tends to stifle commitment to deliver

in fact the simple estimated cost-to-complete, compared with available budget seems most adaptable and applicable to the mixed accounting systems of LHC-type collaborations

Commissioning

Basic steps

Synchronisation


Cosmics

Halo and beam-gas

First beam

Commissioning: in parallel with assembly


must be adapted to the possibilities allowed by the detector configuration




UXC55 PH25 V33-6

Phase 25: From 27-01-06 to 10-02-06

Control system



LHCb's Experiment Control System is in charge of the configuration, control and monitoring of all the components of the online system. This includes all devices in the areas of: data acquisition, detector control (ex slow controls), trigger, timing and the interaction with the outside world



- architectural differences between experiments (slow control & run control) easily obscure that:
- a working, robust slow control system is a pre-requisite for commissioning
 - what really helps is to have infrastructure services, experiment and accelerator all using the same slow control SCADA.

Pre-commissioning: CMS (on surface)

ATLAS pre-commissioning similar

Basic sub-detector commissioning: (2003-2005)

- 0) Basic functionality test of individual detector elements after installation
- 1) Connection to “on-yoke” service lines :water, gas, power etc and readout.
- 2) Connection “slice-by-slice” to SX5 services and control room.
- 3) Detector safety system activated & security checked by GLIMOS and/or TIS
- 4) Gas/cooling/LV power/HV power channel-by-channel checks.
- 5) Checks with Local + Test beam DAQ: channel by channel diagnostics
- 6) Calibration & system fault-finding (noise etc). Test beam DAQ

Advanced commissioning: (2004-2005)


- 7) Test FED's as a data-source (1'st stage of CMS DAQ)
- 8) Test generation of trigger primitives.
- 9) More advanced tests with elements of final DAQ chain.

but with priority to:

**CMS construction. magnet test and basic sub-detector commissioning
Trigger/DAQ system preparation for installation in SCX**


Commissioning: ATLAS phases

CMS underground commissioning similar




Commissioning : Synchronisation (CMS)


the trickiest part of trigger/DAQ system integration



Test beams: combined tests



- Beam Test, including with final bunch structure
 - checks systems and their physics response, separately and in combination.
 - **checks synchronization and establishes first pass phase offsets.**




Commissioning: Timing Model

Timing Model implemented in a Simulation Tool:

- First estimation of timing parameters**
- Help to diagnose synchronization problems**


Timing Diagram (example):

Thousands of timing parameters



- Timing Parameters:**
- Clock Deskewing
 - Bunch Crossing Assignment
 - BC0 adjustment
 - L1A timing adjustment
 - TTCrx parameters
 - TTCci parameters
 - Cable lengths
 - etc.


Commissioning: final phase w/o beam: Cosmic μ 's?



Cosmic muons in ATLAS in 0.01 s

Cosmic event in ATLAS

- One track reconstructed in Muon chambers
- Two tracks reconstructed in Inner Detector
- Will happen every ~ 10 s




Commissioning: first beam

could be quite dirty!!

Dose per unsynchronized LHC beam abort (Gy)

Total dose per accident (duration: 260ns)


M. H.




Commissioning: beam monitor

an absolute pre-requisite for experiment protection & study of beam backgrounds
must have confidence of experiment(s) and machine and be ready for first beam tests of various sensors planned, but appears in no budget line of LHC expts

Beam Conditions Monitor
Protection against fast beam losses
Independent action from the DSS
2 "collars" of sensors around the beam pipe near the pixel region and more sensors located near the TAS
BCM geometry must allow for the detection of showers within the experiment that result from beam deterioration




eg CMS-EST joint project



tests of various sensors planned

Commissioning: first beam

Single beam : beam-gas events



ATLAS estimates:

muons with $E > 100\text{GeV}$: 1 kHz

$E > 1\text{ Tev}$ 10Hz

could give $>10^6$ useful tracks
in every subdetector in a 2-month
period of single beam tuning.

First collisions: very low lumi (but rising to high current per bunch)


synchronisation, check DAQ/filter/offline chain at full rate

calibrations using min. bias distributions and leptons from W,Z decay

first physics distributions (missing E_t ..etc)

Commissioning: CMS DAQ system scaling

1 - 8 x (12.5 kHz DAQ units)



Data to surface:

Average event size	1 Mbyte
No. FED S-link64 ports	700
DAQ links (2.5 Gb/s)	512+512
Event fragment size	2 kB
FED builders (8x8 dual)	64
Technology(2004)	Myrinet

Readout Builders (x8):

Lv-1 max. trigger rate	12.5 kHz
RU Builder (64x64)	.125 Tbit/s
Event fragment size	16 kB
RU/BU systems	64
Event filter power	10 ⁵ SI95
EVB technology (2006)	Open

minimum for start-up due to budget restrictions: progressively commission slices
to match expected L1 rate in first physics runs

Remote Participation

tests are going on to evaluate the best way to use “virtual control rooms” around the world to assist in the commissioning

CMS test beams 2003



A screenshot of a web-based interface for CMS test beams. The interface includes a search bar with date ranges (From: 05.22.2003 12:11 To: 05.22.2003 20:11), a search button, and a list of filters (Operator, Manual-entries ONLY, Header Info Display, Entries Header, Date Created, Date Saved). A dropdown menu for 'Select keywords' is open, showing options like INCLUDE ALL, Shifts, Runs, Conf. Change, Summary, and Notes. Below the search bar, there is a section for 'Annotate This Entry' with details: Date Created: Thursday, May 22, 2003 12:55:08 PM CEST; Date Saved: Thursday, May 22, 2003 1:15:05 PM CEST; Category - Topic - sequence number: PlanPlan - Plan_Log - 62; Operator(s): Dragoslav Lazic; Keyword(s): PLANPLAN_LOG. The main content area contains a 'Brief report from SPS scheduling meeting held Thursday 2003.05.21 at 11h' and several paragraphs of text describing the start-up of PS and SPS, first trials for structured beam injection, and a switch to structured beams for Friday at 13:00. Notes at the bottom mention increased security and CERN closure on Thursday 2003.05.29.

We have new tools for tb2003. There are 2 webcams and a good Polycom system. There is an e-log which allow remote parties to follow the progress. The daily meeting is very useful to increase HCAL participation.

Conclusion

Supercollider experiments are becoming increasingly challenging to build

due to performance parameters, timescale, sociology, external rules and regulations

LHC experiment construction experience shows that it can be done

: tools/expertise exist in the detector-building community

: industry is capable of fulfilling many requirements

Integration will remain a thankless but vital task

Many useful management and QA techniques are applied already at LHC and elsewhere

-:formalism has increased

-add new procedures only if clearly beneficial

- beware divergence between reality and state model

Commissioning: LHC experiment plans will be tested in the coming 3-4 years

- under development now...

- exploit pre-commissioning tests, test-beams, cosmic ray data, beam-gas data
to prepare the experiments for the first colliding beams at LHC