




# SPS Committee

## Status of OPERA/CNGS1

July 6<sup>th</sup> , 2004

1. Achieved and next Milestones
2. Status of detector construction
3. Physics Performance: update
4. Conclusions



Yves Déclais  
on behalf of the OPERA Collaboration



**COLLABORATION**

**36 groups**  
**~ 165 physicists**

**Belgium**

IIHE(ULB-VUB) Brussels

**Bulgaria**

Sofia\_University

**China**

IHEP Beijing, Shandong

**Croatia**

Zagreb University

**France**

LAPP Annecy, IPNL Lyon, LAL Orsay, IRES Strasbourg

**Germany \***

Berlin, Hagen, Hamburg, Münster, Rostock

**Israel**

Technion Haifa

**Italy**

Bari, Bologna, LNF Frascati, L'Aquila, LNGS, Naples, Padova, Rome, Salerno

**Japan**

Aichi, Toho, Kobe, Nagoya, Utsunomiya

**Russia**

INR Moscow, ITEP Moscow, JINR Dubna, Obninsk

**Switzerland**

Bern, Neuchâtel


**Turkey**

METU Ankara

•German participation to OPERA now granted



## The basic unit : the « brick »




- Based on the concept of the Emulsion Cloud Chamber (**ECC**)
- **56 Pb sheets 1mm + 56 emulsion layers**
- Solves the problem of compatibility of large mass for neutrino interactions + high space resolution in a completely **modular** scheme


### ECC are completely stand-alone detectors:

- Neutrino interaction vertex and kink **topology** reconstruction
- Measurement of the **momenta** of hadrons by multiple scattering
- **dE/dx** pion/muon separation at low energy
- **Electron identification** and measurement of the energy of the electrons and photons

ECC Technique validated by the direct observation of  $\nu_\tau$ :  
**DONUT 2000**



**10.2 x 12.7 x 7.5 cm**




# Use of the Electronic detectors



- **trigger** and **localization** of neutrino interactions
- **muon** identification and momentum/charge measurement


➔ need for a **hybrid** detector

## Electronic detectors:




## ECC emulsions analysis:

**Vertex, decay kink e/γ ID, multiple scattering, kinematics**



**Link to mu ID, Candidate event**




**Brick finding, muon ID, charge and p**



# OPERA structure with two Super-Modules

31 target planes / supermodule (in total: 206336 bricks, 1766 tons)



Proposal: **July 2000**, installation at LNGS started in **May 2003**



# Milestones

## Achieved :

- Refreshing facility installed
- First magnet completed
- Brick packaging decision
- BAM ordering
- Scanning speed 20cm<sup>2</sup>/h

## Next Milestones

1. Target installation commissioning: sep 04
2. Emulsion delivery @ LNGS : oct 04
3. BMS automation validation : dec 04
4. BAM commissioning @ factory : feb 05
5. Start brick filling : sep 05



# General Planning

ID	Task Name	Duration	Start	Finish	2004			2005				2006				
					2	3	4	1	2	3	4	1	2	3	4	
226	INSTALLATION IN GS EXPERIMENT HALL C	153.83 w	Mon 2/10/03	Thu 4/27/06	[Gantt bar from 2004 Q2 to 2006 Q1]											
227	C R & ELECTRONIC ROOM	7 w	Fri 4/8/05	Mon 5/30/05	[Gantt bar in 2005 Q2]											
233	BAM	13 w	Mon 6/13/05	Wed 9/14/05	[Gantt bar in 2005 Q3]											
237	SPECTROMETERS (2 MAGNETS & RPC's)	134.03 w	Mon 2/10/03	Mon 11/14/05	[Gantt bar from 2004 Q2 to 2005 Q4]											
238	Preliminary working	15 w	Mon 2/10/03	Wed 5/28/03	[Gantt bar in 2004 Q2]											
239	Veto plane mechanics	2 w	Fri 9/30/05	Fri 10/14/05	[Gantt bar in 2005 Q4]											
240	Veto plane detector	4 w	Fri 10/14/05	Mon 11/14/05	[Gantt bar in 2005 Q4]											
241	Magnet 1	58.35 w	Fri 5/30/03	Wed 8/11/04	[Gantt bar in 2004 Q3]											
274	Magnet 2	95.15 w	Fri 5/30/03	Wed 5/25/05	[Gantt bar from 2004 Q3 to 2005 Q2]											
311	TARGET TRACKERS MOUNTING	72 w	Fri 5/14/04	Fri 11/4/05	[Gantt bar from 2004 Q3 to 2005 Q3]											
330	TARGET WALLS	73.94 w	Wed 8/11/04	Tue 3/7/06	[Gantt bar from 2004 Q4 to 2006 Q1]											
331	SM1	41.18 w	Wed 8/11/04	Fri 6/24/05	[Gantt bar from 2004 Q4 to 2005 Q2]											
410	SM2	32.76 w	Fri 6/24/05	Tue 3/7/06	[Gantt bar from 2005 Q2 to 2006 Q1]											
489	XPC's & PRECISION TRACKERS	79.34 w	Mon 7/5/04	Tue 3/7/06	[Gantt bar from 2004 Q3 to 2006 Q1]											
490	XPC 1	20.88 w	Mon 7/5/04	Tue 11/30/04	[Gantt bar in 2004 Q4]											
496	Precision tracker 1	46.24 w	Wed 3/16/05	Tue 3/7/06	[Gantt bar from 2005 Q1 to 2006 Q1]											
529	XPC 2	23.05 w	Fri 4/8/05	Wed 9/21/05	[Gantt bar in 2005 Q2]											
535	Precision tracker 2	18 w	Mon 7/25/05	Tue 11/29/05	[Gantt bar in 2005 Q3]											
568	CABLING (detector to control room)	24.35 w	Wed 6/15/05	Tue 12/6/05	[Gantt bar in 2005 Q4]											
571	MANIPULATORS	44.8 w	Wed 5/18/05	Thu 4/27/06	[Gantt bar from 2005 Q2 to 2006 Q1]											
572	SM1 cavern side	13 w	Wed 5/18/05	Fri 8/19/05	[Gantt bar in 2005 Q2]											
578	SM1 corridor side	13 w	Thu 6/30/05	Fri 9/30/05	[Gantt bar in 2005 Q3]											
585	SM2 cavern side	25.8 w	Fri 9/30/05	Thu 4/27/06	[Gantt bar from 2005 Q4 to 2006 Q1]											
589	SM2 corridor side	17.43 w	Wed 11/30/05	Thu 4/27/06	[Gantt bar in 2006 Q1]											
594	COMMISSIONING WITHOUT BRICKS	27.35 w	Wed 6/15/05	Tue 1/17/06	[Gantt bar in 2005 Q4]											
597	ECC BRICK MANUFACTURING WITH BAM	43 w	Fri 9/30/05	Wed 8/30/06	[Gantt bar from 2005 Q4 to 2006 Q3]											
599	WALL BRICK FILLING (2b/min 8h/day)=960 bricks)	47.2 w	Mon 10/3/05	Fri 9/29/06	[Gantt bar from 2005 Q4 to 2006 Q3]											
600	SM1 brick filling	21.6 w	Mon 10/3/05	Fri 3/24/06	[Gantt bar from 2005 Q4 to 2006 Q1]											
602	SM2 brick filling	21.6 w	Thu 4/27/06	Fri 9/29/06	[Gantt bar in 2006 Q2]											
604	COSMIC DATA TAKING WITH BRICKS	20 w	Mon 10/10/05	Tue 3/21/06	[Gantt bar from 2005 Q4 to 2006 Q1]											
605	FULL DETECTOR COMPLETED	0 d	Fri 9/29/06	Fri 9/29/06	[Point at 2006 Q2]											
606	CNGS Beam delivery	0 d	Wed 4/19/06	Wed 4/19/06	[Point at 2006 Q1]											
607	OPERA RUNNING	94.6 w	Mon 5/3/04	Mon 4/24/06	[Gantt bar from 2004 Q3 to 2006 Q1]											
608	OPERA LNGS external building	60 w	Mon 5/3/04	Wed 7/27/05	[Gantt bar from 2004 Q3 to 2005 Q2]											
609	Emulsion processing laboratory	20 w	Thu 7/28/05	Fri 12/16/05	[Gantt bar in 2005 Q4]											
610	Processing tests	12 w	Mon 1/9/06	Fri 3/31/06	[Gantt bar in 2006 Q1]											
611	OPERA brick processing cycle	0.8 w	Wed 4/19/06	Mon 4/24/06	[Gantt bar in 2006 Q1]											
612	First brick extraction	1 d	Wed 4/19/06	Wed 4/19/06	[Point at 2006 Q1]											
613	Brick cosmic rays exposure	1 d	Thu 4/20/06	Thu 4/20/06	[Point at 2006 Q1]											
614	Emulsion development	1 d	Fri 4/21/06	Fri 4/21/06	[Point at 2006 Q1]											
615	Emulsion shipping to scanning labs	1 d	Mon 4/24/06	Mon 4/24/06	[Point at 2006 Q1]											

3/24/06  
9/29/06





# Magnet installation







# OPERA in Hall C : end of june 04









# SM1 & SM2 Superstructures in the factory





# RPCs : tests and installation

- End installation 1st Spectrometer on May 19th, with success
- End production RPC but some contingency due to high level rejection (20%)
- End production of strips
- Electronics in a good shape (FEB with some month delay, DAQ controller ready)
- Ready to start installation 2nd Spectrometer in September







# RPCs : Tests in situ

Gaz :  $\text{Ar}/\text{C}_2\text{H}_2\text{F}_4/\text{i-C}_4\text{H}_{10}/\text{SF}_6=75/20/4/1$  (premixed bottles)

- The counting rates at the operating point are of the order of few  $\text{Hz}/\text{m}^2$  (to be compared with  $30\text{Hz}/\text{m}^2$  without shielding And  $200\text{-}400\text{ Hz}/\text{m}^2$  outside the cavern)
- The counting rates are higher for the eastern RPC (near the lateral wall of Hall C)
- There is not a plateau, but an exponential dependence on the operating voltage








# Precision tracker

- 96 modules / Supermodule
- 2 modules in test @ DESY
- electronics tested (front end and TDC)
- mass production ready





## Precision Tracker : funding issues

- Present BMBF funding period: jan2004 – june2006  
Uni Hamburg receives funds for march2004-june2006  
~ 1.05 M Euro  
(asked in 2004 for 1.6 M Euro:  
invest 900k, salaries 520k + travel & transp.)

Money flow from BMBF:  
2004: 370kEuro  
2005: 490kEuro  
2006: 190kEuro

Note:  
No funding for full gas system  
(only development & prototype)  
HERA-B muon gs ?

this is the cost for 1 SM

(~2/3 of full material cost, ~1/2 salaries, 1/2 tt)

(Updated) need to complete full detector in time:  
330kEuro (Material) + 370kEuro (man power) = 700kEuro



## Target Tracker : deliveries

- mass production ongoing for :  
for scintillator strips, fiber, MAPMT, electronics
- MAPMT tests ongoing : efficiency OK

- 3 PMT's rejected from 32 PMT's delivered in 2003
- 3 PMT's rejected from first 32 PMT's delivered in 2004
- Only 2 PMT's rejected from last 96 PMT's




After few iterations and feedback given to Hamamatsu, the PMT quality is improving.




# Gain for the first 160 MAPMTs

corr per channel




chcorr	
Entries	9664
Mean	1.452
RMS	0.3239

max.corr per PM




corrhist	
Entries	151
Mean	2.206
RMS	0.2855

av.corr-factors per channel







av.gain per channel










# Quantum efficiency for the first 160 MAPMTs











# Dark current





# Cross Talk










# Target Tracker Modules Production

86 produced over 500








# Target Tracker : Modules calibration

- 2 tables ready (equipped now with "final" electronics):
  - light tightness,
  - light injectors,
  - number of photoelectrons.



module storage area (cookie polishing, light tightness tests)











scanning tables





# Status of the calibration

## Module 36




but since some time...








# Target Tracker : Wall pre-assembly








# Target tracker : wall 1 mounting @ Strasburg



hooks for module hanging in the box

hooks for module hanging in the box



8 modules inside







# Target tracker : wall 1 mounting @ Strasburg






# Target Tracker : wall insertion



"hook" under study, construction and certification by a private company

during insertion of a TT wall

walls already inserted









# Alignment with Photogrammetry

- Closed range targeted digital photogrammetry, widely used at CERN for the survey of LHC detectors

Environment with small free space around the detectors, large objects of 15-20 m have to be measured from a few m, during installation phase

Many points to be measured (dense microgeodetic network)

- Agreement between the CERN EST division and the LNGS to setup a service at LNGS (technology transfer and training of local people)







# TT wall alignment : full scale training

CERN+LNGS experts


Targets on a TT biplane:



Targets in the precision holes of the end-caps 2/end-cap:  $2*4*4=32$  total



Targets on the *croisillons*, each doublet surveys the positions of the crossing point of 4 modules:  $9*2=18$  targets in total





## Measurements taken in Strasbourg on the first TT biplane



Photogrammetric Measurement 09.-11.06.2004



- Test and optimize the procedure on full size prototype
- Study as a function of the distance from the object
- Study of the planarity of the TT biplane
- Study of the rigidity during handling of the TT biplane
- Training of LNGS surveyors



Survey technique  
successfully applied  
to the TT biplane







## Study of the deformations of the TT biplane

Used standard targets + extra 35 surface coded targets

Handling at maximal acceleration of the crane + reiterated shock cycles



No displacements observed within 0.2 mm, the TT behaves like an elastic object retaking its initial shape after handling



## Brick Wall : production


Tendering (start)	MAY 2003
Tendering (end)	OCT 2003
Production contracts signed	JAN 2004
First wall prototype built	<b>JUL 2004</b>
First wall delivered at LNGS	<b>SEP 2004</b>
Last wall delivered at LNGS	<b>JUN → DEC 2005</b>




Turnbuckles (commercial parts)	✓ @ LNGS
Columns, Brackets, Pins, Bottom Rails (COMIT)	✓ @ LNGS
Insertion tool (LNF)	✓ @LNF
Bolts (commercial parts)	Ordered (@LNF 5 July)
Top Rails (CECOM, LMM)	Built (@LNGS 8 July)

Reference marks positioning (for alignment)	✓ <b>JUNE 2004</b>
Rails installation/alignement 1 <sup>st</sup> SM	<b>JUL/AUG 2004</b>
Walls installation/alignement 1 <sup>st</sup> SM	<b>SEP 04 → JUN 05</b>
Rails installation/alignement 2 <sup>nd</sup> SM	<b>JUN/JUL 2005</b>
Walls installation/alignement 2 <sup>nd</sup> SM	<b>JUL 05 → FEB 06</b>

# Refreshing facility in the TONO mine (Japan)



**Film lay out on the plates**



**Film installation**

**Vacuum packing**




Room Size  
4.5m × 4.5m × 20m



# Refreshing facility in the TONO mine (Japan)

Running





# Brick

**Lead choice:** Ternary Leads (Pb/Ag/Al or Pb/Ag/Sn)

→ Pb/Ca may damage emulsion : water vapor on Ca produces Hydrogen gas

**Mechanical packaging choosen (long term tests performed):**

→ Laminated film are fragile and vacuum may be lost during brick manipulation




→ pressure maintained by mechanical structure and high resistance scotch tape

→ light tightness obtained by Al scotch tape






# Details of Mechanical Packaging





# *BAM + BAM site Design*







# *The piling station of the BAM*




First mechanical tests of lead and emulsion manipulation with anthropomorphic ABB robot have started to check the precision in the piling operation

Further studies are needed on:

- vacuum sucking device
- photographic effects



# *The BAM site at LNGS*



Preparation of the by-pass site has **started** in March '04  
Main civil engineer done in May-June '04  
Tender for air conditioning system closed in March '04,  
to be delivered by Sept '04  
Electrical network and safety systems to be delivered in  
July '04  
*Monthly meeting with BAM and LNGS engineers to  
monitor the status of the work in progress.*




# *BAM schedule*

✓ Final specifications:	December 2002
✓ End of market search:	March 2003
✓ Technical audit:	April 2003
✓ Call for tenders:	May to October 2003
✓ Firm selection:	November 2003
✓ Ordering:	December-January 2004
✓ Design, Construction and Tests in the firm:	February 2004 to March 2005
Delivery at Gran Sasso laboratory:	April 2005
Assembly, installation:	May 2005
Production acceptance tests at Gran Sasso:	June to August 2005
Brick mass production:	September 2005 to September 2006



# Changeable sheet

- R&D ~2004-Oct
  - BG rejection
    - Distortion : distortion itself, precise measurement, packing
    - Self-Refresh : parameter study
  - Aging test at high humidity
    - sensitivity , fog , etc.
- CS packing machine development ~2004-May
- Production 2005-May ~ 1000CS/day
  - Humid packing at Nagoya.
  - Initialization at Gran Sasso (self-refresh acceleration, 30degC 1month etc)




- **By tuning the development procedure the distortion is removed intrinsically.**
  - at the level of  $\sigma_{\theta} < 2\text{mrad}$ .
  - **Now observed distortion is dominated by the stage accuracy and measurement.**



# Brick Manipulator System


- Portico ready for tests DZ & DY: **June 04**
- Platforms complete: **September 04**
- Loading station 1 constructed: **June 04**
- Loading station fully equipped: **mid-October 04**
- First basket: **July 04**
- VV final vehicles: **October 04**
- Loading station 2: **December 04**
- Portico 2 installation: **February 05**








# BMS : first system constructed in Annecy





# BMS Supervisor






# Emulsion processing @ LNGS

## The new building

- Meetings between Company's management and GS staff to fully define the project
- 'Work delivery' (*consegna dei lavori*) on May, 18th
  - ➔ formal delivery date is 15 months since this date!
- Area cleared and delimited (also our Cosmic-ray hut displaced...)
- Excavation expected to start this week
- We are expected to provide Fe for Cosmic-ray pit shielding by summer

## The prototype chain

- Test site hall assigned and prepared for OPERA
- Main structure assembled, several details defined
  - ➔ Ready and equipped for full scale tests by July, then "automation" program will start








# Status of the European Scanning System

(Bari, Bern, Bologna, Lyon, Napoli, Neuchâtel, Roma, Salerno)

- New CMOS camera up to 500 fps
- New Image processor Matrox Odyssey and more powerful PCI-X workstation
- Same Optics (Nikon) and Mechanics (Micos) **now as industrial productions**
- New asynchronous DAQ software




**Scanning lab being installed @LNGS**


- Scanning speed  $\sim 20 \text{ cm}^2/\text{h}/\text{side}$
- Single side microtrack finding efficiency  $\sim 95\%$
- Sheet-to-sheet alignment precision (8 GeV/c  $\pi$ s)  $\sim 0.5 \mu\text{m}$
- Angular resolution  $\sim 2\text{mrad}$



# Scanning Performances




dxfitc



dxfitc

**Aligned beam volume-tracks  
having at least 5 base-tracks.  
Correcting residual sistematic  
errors.**



# Japanese Scanning System: image processing

Camera Head + CCU



## Ultra High Speed CCD Camera for S-UTS


- 512(H)×504(V) pixels
- 3k frames/sec
- Digital output via LVDS, 1.3Gbyte/sec

New Front-End FPGA boards  
(under debug)





# OPERA Software Chain





# OPERA Software

- General framework : ROOT/VMC
- Still a lot of work to complete :
  - the integration of analysis tools
  - the common (Japanese and European) format for data coming out from scanning systems (micro tracks and pulse height)
  - the convergence between different emulsion reconstruction algorithms
  - the central database
  - the documentation, presently very incomplete
- No serious worry for the schedule, but limited manpower
- Better access to CERN computing resources



## $\tau$ detection efficiencies (in % and including BR)

Channels considered at the time of the CNGS approval in 1999 :

$\tau \rightarrow e$  (DIS+QE, long) 3.0

$\tau \rightarrow \mu$  (DIS+QE, long) 2.6

Overall efficiency  $\varepsilon = \underline{5.6}$

*DIS long*      *QE long*      *DIS short*      *Overall\**

$\tau \rightarrow e$	2.7	2.3	1.3	3.4
$\tau \rightarrow \mu$	2.4	2.5	0.7	2.8
$\tau \rightarrow h$	2.8	3.5	-	2.9
<b>Total</b>	<b>8.0</b>	<b>8.3</b>	<b>1.3</b>	<b>9.1 %</b> Eff* BR

\* weighted sum on DIS and QE events

### Improvements under study:

- use of a changeable sheet on the back side of the brick
- Brick finding strategy : +10%
- channel  $\tau \rightarrow 3$  prongs (1.0% eff, including BR 15%) : +10%





# Improvements in the brick location analysis


- **Integration** in the algorithm of all the informations provided by the detector:  
Energy flow, Tracking + vertexing, Muon identification
- **Classification** of the events in categories:  
with muon (small/large hadronic energy)  
without muon (dominantly/not dom. electromagnetic shower)

In order to optimize both the NN energy flow analysis and the tracking analysis

- **Combination** of the wall probabilities from the NN energy flow analysis with the 3D vertex probabilities in order to produce a **3D brick probability chart**
- **Sequential extraction** and analysis of the bricks following the order of the probability chart

Efficiency improved with minimal losses of the target mass

# Combined NN + tracking probability chart for a typical $\tau \rightarrow \mu$ event





# Efficiency for the: $\tau \rightarrow \mu$ channel

<u>BR</u>	<u>Evt long</u>	<u><math>\epsilon</math> Localization</u>	<u>Kink+ kinematics</u>	<u>Id <math>\mu</math> + ECC connection</u>	<u>Others</u>
0.176	0.39	0.73	0.73	0.80	0.96 $\rightarrow$ 2.8%

6.8%

Application of the 3D chart

Additional fraction of extracted bricks

Extraction strategy:	$\tau \rightarrow \mu$	$\tau \rightarrow e$	$\tau \rightarrow h$	
Only the Highest Prob. Brick (HPB)	73.5%	75.4%	64.2%	
HPB + second most probable brick (SMPB) if $P1-P2 < 0.1$	+1.0%	+3.0%	+4.7%	$\rightarrow$ 0.3%
HPB + SMPB if $P1-P2 < 0.2$	+2.0%	+5.0%	+6.9%	$\rightarrow$ 0.4%
HPB + SMPB if $P1-P2 < 0.3$	+2.8%	+5.8%	+8.2%	$\rightarrow$ 0.5%
HPB + SMPB ( $P2 > 1\%$ )	+8.1%	+9.7%	+12.0%	$\rightarrow$ 1.2%
Sequential extraction of all the bricks in the list (with $P > 1\%$ )	+9.6%	+12.0%	+16.1%	$\rightarrow$ 1.9%

Net efficiency gain  $\rightarrow$  +7.7% + 10.1 +14.2%

Minimal reduction of the target mass





# Historical summary of Brick finding efficiencies

OPERA proposal (2000)

Inclusion of nuclear effects  
(-10% avg. eff. loss ) and  
analysis retuning (2002)

Sequential, probability  
ordered, extraction of  
all the bricks in the 3D  
chart ( $P > 1\%$ ) until the  
vertex is found (2004)

$\tau \rightarrow \mu$	$\tau \rightarrow e$	$\tau \rightarrow h$
73.0%	80.1%	69.8%
65.1%	74.0%	63.2%
81.2%	85.5%	78.4%

The last numbers are corrected for the target mass reduction due to the multi-brick extraction

- Single brick extraction efficiencies recovered the losses due to the inclusion of nuclear effects and came back to the Proposal values
- The application of the 3D probability chart allows to increase by 10% the number of  $\tau$  events (weighted effect)



# Expected number of background events

(5 years run, nominal intensity)

(in red : possible improvements)	$\tau \rightarrow e$	$\tau \rightarrow \mu$	$\tau \rightarrow h$	total
<b>Charm background</b>	.210 <span style="color: red;">.117</span>	.010 <span style="color: red;">.007</span>	.162 <span style="color: red;">.160</span>	.382 <span style="color: red;">.284</span>
<b>Large angle <math>\mu</math> scattering</b>		.116 <span style="color: red;">.023</span>		.116 <span style="color: red;">.023</span>
<b>Hadronic background</b>		.093 <span style="color: red;">.093</span>	.116 <span style="color: red;">.116</span>	.209 <span style="color: red;">.209</span>
<b>Total per channel</b>	.210 <span style="color: red;">.117</span>	.219 <span style="color: red;">.123</span>	.278 <span style="color: red;">.276</span>	.707 <span style="color: red;">.516</span>

30% possible background reduction

### 1. Charm background :

- Being revaluated using new CHORUS data: cross section increased by 40%
- $\pi\mu$  id by  $dE/dx$  would reduce this background by 40%
- ⇒ being tested at KEK and this autumn at PSI (pure beam of  $\pi$  or  $\mu$  stop)

### 2. Large angle $\mu$ scattering :

- Upper limit from past measurements used so far
- Calculations including nuclear form factors give a factor 5 less
- ⇒ will be measured in 2004 in X5 beam with Si detectors

### 3. Hadronic background :

- Estimates based on Fluka standalone : 50% uncertainty
- Extensive comparison of FLUKA with CHORUS data and GEANT4 would reduce this uncertainty to ~15%



# $\nu_{\mu} \rightarrow \nu_{\tau}$ sensitivity

full mixing, 5 years run @  $4.5 \times 10^{19}$  pot / year

	signal ( $\Delta m^2 = 1.9 \times 10^{-3} \text{ eV}^2$ )	signal ( $\Delta m^2 = 2.4 \times 10^{-3} \text{ eV}^2$ )	signal ( $\Delta m^2 = 3.0 \times 10^{-3} \text{ eV}^2$ )	BKGD
<b>OPERA</b> 1.8 kton fiducial	6.6(10)	10.5(15.8)	16.4(24.6)	0.7(1.1)
+ brick finding + 3 prong decay	8.0(12.1)	12.8(19.2)	19.9(29.9)	1.0(1.5)
Background reduction	8.0(12.1)	12.8(19.2)	19.9(29.9)	0.8(1.2)

(...) with CNGS beam  
upgrade (X 1.5)






# Sensitivity versus Background

Opera with  
expected  
background  
improvements  
-30%

Opera, half  
background



SK 90% CL (L/E analysis)



# Sensitivity versus Beam Intensity

Opera with foreseen improvements  
And beam\*5


Opera with beam\*2

Opera with beam  
upgrade (1.5) no  
background  
reduction

Opera with  
beam\*3

Opera, nominal  
beam but half  
background

Opera nominal





# Conclusions

- **despite the difficulties @ LNGS and the limited support in Home Institutions**  
**the installation of the OPERA experiment is following the expected schedule**
- **the completion of the first SuperModule is foreseen in feb 06**  
**and the second in september 06**  
**→ we need a physics run in 2006 to start the physics program**
- **to cover the allowed range of  $\Delta m^2$  from SuperK analysis**  
**→ better efficiency and background reduction for OPERA are needed : in progress**  
**→ more protons onto the CNGS target are needed:**  
**either by increasing the number of CNGS cycles**  
**or (and) increasing the proton intensity in the SPS as soon as possible**