

BNL Service Challenge 3 Status Report

Xin Zhao, Zhenping Liu, Wensheng Deng, Razvan Popescu, Dantong Yu and Bruce Gibbard

USATLAS Computing Facility
Brookhaven National Lab



Services at BNL



- FTS (version 2.3.1) client + server and its backend Oracle and myproxy servers.
 - □ Reliable in controlling CERN to BNL data transfer, after several rounds of bug fixes
 - ★ Short timeout value caused excessive failures
 - ★ Incompatibility with dCache/SRM.
 - □ Still does not support DIRECT data transfer between CERN and BNL dCache data pool servers (dCache SRM third party data transfer)
 - # Data transfers go through a few dCache GridFTP door nodes, a scalability issue
 - # Had to move these door nodes to non-blocking network ports to distribute traffic
 - Both BNL and RAL discovered that the number of streams per file could not be more than 10, (Is this intended?)

Network to CERN:

- □ Network for dCache was upgraded to 2*1Gb/s in June.
- □ Shared link to CERN with Round Trip Time: >140 ms
- Occasional packet losses observed along BNL-CERN path
- □ 1.5 Gb/s aggregated bandwidth observed by iperf with 160 TCP streams.



Services at BNL




- dCache/SRM (V1.6.5-2, with SRM 1.1 interface, Total 332 nodes with about 170 TB disks, Multiple GridFTP, SRM, and dCap doors): USATLAS production dCache system.
 - Experienced high load on write pool servers during high rate data transfers
 # Fixed by replacing the EXT file system with XFS file system.
 - Core server crashed once. Reason was identified and fixed
 - □ Small buffer space (1.0TB) for data written into dCache system
- **BY LFC (1.3.4) client and server was installed at BNL**
 - □ Server was installed and basic functionalities tested: Ifc-Is, Ifc-mkdir etc.
 - □ Will populate LFC with the entries from our production Globus RLS server
- DPM is being deployed internally at BNL and under evaluation.
- An agent box was setup for ATLAS experiment software




Transfer Plots

Castor2 LSF plug-in problem










Data Transfer Status





00:00

06:00

50 M

Out

In

18:00

12:00

Some Issues



Service Challenge Effort

- □ Activities have included tuning network pipes, optimizing the configuration and performance of BNL production dCache system and its associate OS & file systems, installation and integration of other SC3 components
- Major effort was required to stabilize newly deployed FTS, dCache and network infrastructure.
- □ Effort level does seem to be decreasing as services became stable.
- Resources are shared by experiments and users.
 - □ CERN SC3 infrastructure is shared by multiple Tier 1 sites
 - Due to variations between Tier 1's, data transfer needs to be individually optimized based on a Tier 1 site's characteristics, network RRT, packet loss rates, other experiment specific requirements, etc.
 - □ At BNL, network and dCache are also used by production users.
 - * Need to closely monitor the SRM and network to avoid impacting production activities.
- At CERN, James Casey seems almost single handedly to be answering email, setting up systems, reporting problems and running data transfers
 - Does he need more help?



Plans for Remainder of Throughput Phase



* Tier 2 SC3 Participation proceeding slowly

- □ Continue to evaluate DPM at BNL for US ATLAS Tier 2 centers
- □ Limited work on going at selected Tier 2 sites
- □ Still hope to transfer data from/to two Tier 2 sites with BNL FTS instance: Boston University (GridFTP server), University of Chicago (GridFTP/DPM?)

SC3 Tape Transfer

- □ Small scale transfer test between Tier 0 ~ BNL dCache/HPSS with BNL FTS. (July 18~July 22)
- □ Plan to borrow tape resources for actual data transfer exercise

