



LHCb & SC3

Plans for SC3 sample jobs; SC3 resource needs; Planning updates; Current problems and issues (SC3 and LCG)

R.Graciani





- Aims
- Phases & Schedule
- Requirements
- Current Issues





- Test Data Management system
 - Bulk scheduled operations
 - Real Time data transfers
- Interaction between Data Management and Workload Management systems





- Preparation for SC3 Service phase
- Tuning and testing phase
- Functional test of later procedures
- No significant computing or network resources will be needed
- Already started





- Bulk Scheduled data movement:
 - a) Stripped data replication from CERN to all Tier1's:
 - ~1 TB of data (50k files, including event tag collections, large and small files).
 - b) Data replication from CERN to all Tier1's:
 - ~8 TB of data (500 MB/file), ~30% of 2008 req.
 - c) Removal of DSTs via LFN's.
 - d) Data replication from each Tier1 to CERN and all other Tier1's
 - ~40% of 2008 req.

CERN 20-July-2007

LHCb & SC3



Phase 1: Req. & Schedule



- Phase 1.a):
 - may be included as part of the Phase 0 at the end of September.
 - ~1 TB permanent space on fast access storage at each Tier1 (disk with SRM interface preferred).
- Phase 1.b):
 - 2 weeks: 40 MB/s out of CERN (6.5 MB/s into Tier1).
 - ~8 TB temporary space on MSS at each Tier1.
 - Starts in October.
- Phase 1.c):
 - After each cycle of phase 1.b) is completed.
- Phase 1.d):
 - 2 weeks: 3.3 MB/s point to point.
 - − ~8 TB temporary space on MSS at each Tier1 + CERN.
 - Second half of October.





- Real Time data movements + WMS:
 - MC production on Tier2's.
 - Online stripping on Tier1's (+ CERN).
 - Replication of selected events to all Tier1's + CERN.
 - Limited User Analysis at Tier1's (+ CERN).
- File Catalog stress testing:
 - LFC and Fireman.
 - 10 M "LFN's" and 100 M "PFN's".



Phase 2: Req. & Schedule



- Starting mid of November and running until the end of the year.
- Req:
 - 800 x 2.4GHz WN's for the MC production.
 - 4 x 2.4 GHz WN's at each Tier1 (+ CERN) for the stripping.
 - 10 TB distributed storage for full MC sample.
 - 350 GB at each Tier1(+ CERN) on fast access storage (pref. Disk with SRM).
- User analysis will start using data from phase
 1.a). High level LHCC milestone to be met.

CERN 20-July-2007



Other Requirements



- All 6 LHCb Tier1's participate (+ CERN):
 - CNAF, FZK, IN2P3, NIKHEF, PIC & RAL.
- File Catalogs:
 - Dedicate LFC (CERN + ≥1 R.O.).
 - Dedicated Fireman.
- **FTS**:
 - Central Server + Client tools.
- Storage:
 - MSS with SRM interface + gridFTP server.
- Dedicated hosting CE for VO specific agents.



Current Issues



- Working on LCF integration:
 - Catalog population.
 - Interaction with DIRAC and LCG WMS.
- FTS first tests.
- User Analysis:
 - Adding GRID certificates and proxies to DIRAC.
 - Including roles to manage access to different DIRAC services.





- Minor modifications in schedule with respect to SC3 workshop (to accomodate all experiements).
- Testing up to end of September
- Bulk data movement in October
- Online data tranfers and processing since mid November
- Others:
 - File catalog testing
 - User Analysis