

RAL Plans for SC2


Andrew Sansum
Service Challenge Meeting
24 February 2005



UKlight & the extended development network -Phase 1 & Phase 2 Warrington C-PoP Leeds C-PoP Leeds University Lancaster University 2 x Dark Fibre Development Network GSR 10Gbft8 Production GSR. K2 Production GSR Production GSR 10Gblt8 University of Manchester 10Gbits 10Gbft% Cambridge University Reading C-PoP London C-PoP 2 x 10 Gblt/s 10GbHts odiction GSR Ci Dark Fibre 2 x 10 Gblt/s RAL Netherlight 10Gbitts ULCC 10Gbfts Starlight Ci Development Ci Development K2




Site Network






Tier1 LAN







dCache Evolution



24 February 2005

RAL SC2 Plans





SC2 Disk Server



2*1Gbit uplink (1 in use)

Server: dual 2.8Ghz Xeon

7501 chipset

U320 SCSI

1 Lun per device, ext2

EonStore

Eonstore

15+1 RAID 5 250GB SATA

120MB/s

120MB/s





dCache Versions

```
d-cache-core-1.5.2-33
```

d-cache-lcg-4.0.0-1

d-cache-opt-1.5.3-15

d-cache-client-1.0-34

vdt_globus_info_server-VDT1.1.14rh7gcc3-4

vdt_globus_essentials-VDT1.1.14rh7gcc3-4.lcg1


vdt_globus_sdk-VDT1.1.14rh7gcc3-4.lcg1

vdt_globus_info_essentials-VDT1.1.14rh7gcc3-4






Production dCache SRM






CMS dCache Network Load



At peak: 500Mb/s sustained until RAL caught up with CERN stager. Not yet optimised - RAL lightly loaded




CMS Production Network Load



At peak: 500Mb/s sustained (full end to end including cataloguing etc) until RAL caught up with CERN stager. Not yet optimised - RAL lightly loaded



SRM Server Load




Postgres CPU load very high - mainly waiting on update. Needs tuning?





Postgres Server Load








SC2 Infrastructure


- Build another PRODUCTION dCache SRM
- Build from kickstart therefore quick
- Build on PRODUCTION SRM experience
- Build in production monitoring
 - Exception monitoring (SURE/NAGIOS)
 - Ganglia Monitoring
 - helpdesk
 - Etc etc
- Build modular avoid bottlenecks
- Decouple network transfers from disk servers allows easier network/kernel tuning
























Data Pathways

Experiment Production Service Challenges





MSS Integration

- Back end from dCache to MSS (STK plus RAL ADS) written and tested. Just beginning experiment testing (CMS initially).
- MSS still bottlenecked at MSS cache disk probably will not exceed 60MB/s (writing) until
 new hardware delivered (in time for July).
- Will not commit to MSS testing for SC2, but may turn dCache MSS back end on at some stage in SC2 and see what we an achieve.





Timetable

Network

- Access agreement for UK Light
- Peering agreed with NetherLight
- Attach to UKLIGHT 25 February
- Start throughput tests to CERN, W/B 28 Feb?

Hardware

- All hardware now drained from production
- Extra NICs purchased
- Disk Stress tests complete H/W ready to deploy

dCache SRM

- Just starting deployment (2-3 days)
- Ready for SRM tests from CERN to RAL W/B 7 March
- Peak load test 2Gb/s sometime in W/B 14 March

