



LHCb SC3 Status

GDB 12/Oct/2005 Bologna

R. Graciani





Setup phase (July-September):

- Service phase (October):
 - CERN ⇒ Tier1's

Summary





- Work done by:
 - Marianne Bargiotti
 - Adria Casajus
 - Gianluca Castellani
 - Ricardo Graciani
 - Gennady Kuznetsov,
 - Stuart Paterson,
 - Juan Saborido
 - Roberto Santinelli (LCG support)
 - Andrew C. Smith,
 - Andrei Tsaregorodtsev,
 - Tier1 support personnel + LHCb Contact @ Tier1
- DIRAC TransferAgent (FTS).
- FTS Channels.
- SRM endpoints.






- LHCb always had continuous effort joint with LCG about production and LCG resources
- LHCb decided to enlarge the PASTE group towards a "Task Force" including:
 - More representatives from Grid Deployment
 - More representatives from Service developers
 - More LHCb contacts
- The Task-Force/PASTE group holds weekly meetings (Tuesday @ 10:00)
- During SC3, daily (working days) meetings @ 16:00



DIRAC TranferAgent (I)







DIRAC TransferAgent (III)





- Gets transfer requests from Transfer Manager;
- Maintains the pending transfer queue;
- Validates transfer requests;
- Submits transfers to the FTS;
- Follows the transfers execution, resubmits if necessary;
- Sends progress reports to the monitoring system;
- Updates the replica information in the File Catalog;
- Accounts for the transfer characteristics:
 - Start/execution time;
 - Effective bandwidth.





- July 7th: first transfer submitted on CERN-CERN channel using the CLI on the fts-lhcb-test machine.
- July 8th: transfers possible to INFN and GridKA (other endpoints not fully functioning)
- August 8th: FTS Client installed on development machine (install instructions on twiki missing mention of CGSI_gSOAP rpm).
- August 10th: DIRAC transfer agent able to resolve source and target SURLs and submit transfers to FTS through client.
- August 29th: Started intstall of new FTS 1.3 client on development machine. Initially not possible to perform transfers to production endpoints at the Tier1s as not mentioned in the channel configurations.
- August 31st: DIRAC transfer agent is able to take a list of LFNs and target sites then create and submit FTS jobs.





September 9th:

- FTS transfers integrated to use request DB within DIRAC.
- Monitoring of FTS transfers using the 'glite-transfer-status' CLI gives information on all files in transfer. This is parsed and completed files and failed files are recorded in the request DB.
- Logic implemented to register completed files in the catalogs.

September 19th:

 DIRAC transfer agent implementing resubmission of files that have failed to transfer successfully.

September 29th:

- sending transfer accounting information on completion of FTS jobs.
- First messages send to monitoring service.





	SRM endpoint	
	Production	SC3
CERN	castorgrid.cern.ch	castorgridsc.cern.ch
CNAF	castorsrm.cr.cnaf.infn.it	sc.cr.cnaf.infn.it
GRIDKA	f01-015-103-e.gridka.de	
IN2P3	ccsrm.in2p3.fr	
PIC	castorsrm.pic.es	castorsrmsc.pic.es
RAL	dcache.gridpp.rl.ac.uk dcache-tape.gridpp.rl.ac.uk	
SARA/NIKHEF	srm.grid.sara.nl	

	MSS Area	
	Permanent	Temporary
CERN	/castor/cern.ch/grid	/castor/cern.ch/grid/lhcb/sc3
CNAF	/castor/cnaf.infn.it/grid/lcg	/castor/cnaf.infn.it/grid/lcg/lhcb/sc3
GRIDKA	/pnfs/gridka.de	/pnfs/gridka.de/sc3
IN2P3	/pnfs/in2p3.fr/data/lhcb/disk	/pnfs/in2p3.fr/data/lhcb/hpss/lhcb/sc3
PIC	/castor/pic.es/grid	/castor/pic.es/sc3
RAL	/pnfs/gridpp.rl.ac.uk/data	/pnfs/gridpp.rl.ac.uk/tape/lhcb/sc3
SARA/NIKHEF	/pnfs/grid.sara.nl/data	/pnfs/grid.sara.nl/data/lhcb/sc3



Service Phase



- Phase 1: (Data Moving)
 - Demonstrate Data Management to meet the requirements of the Computing Model
 - October
- Phase 2: (Data Processing)
 - Demonstrate the full data processing sequence in real time
 - Demonstrate full integration of the Data and Workload Management subsystems
 - Mid-November + December



Phase 1 goals (a,b)



- a) Distribute stripped data Tier0 ⇒Tier1's (1-week). 1TB
 - The goal is to demonstrate the basic tools
 - Precursor activity to eventual distributed analysis
- b) Distribute data Tier0 ⇒ Tier1's (2-week). 8TB
 - The data are already accumulated at CERN
 - ❖ The data are moved to Tier1 centres in parallel.
 - The goal is to demonstrate automatic tools for data moving and bookkeeping and to achieve a reasonable performance of the transfer operations.



Chronology (III)



- The 606 files (DC04/v2) to be transferred were broken up into 6x101 file blocks. Half of this data already existed at CNAF and PIC.
- October 4th:
 - Started transfer 1 block to sites (permanent).
 - One block submitted to RAL channel. This transfer was successful with only 8 files failing (now only 2).
- October 5th:
 - 2 blocks submitted to RAL channel at once. Also successful.
- October 6th :
 - 3 blocks to IN2P3.
 - One of these jobs exposes a bug in FTS where an error string is returned with the status when performing a 'glite-transfer-status -I' for a transfer of 100 files (bug submitted to savannah). This causes failure in parsing of the output.
 - 1 block submitted to both RAL and IN2P3 channels with success.
 - 4 blocks to SARA channel also successful. Some of these files registered with wrong PFN in LFC due to a Transfer Agent configuration problem.




Thursday, October 6th











Chronology (IV)



October 7th:


- 6 blocks submitted to FTS in single job on GridKA channel. Transfer Agent truncates this request to 450 file request (still being investigated although suspected to be problems with LFC host).
- Both FTS and Transfer Agent were able to cope with this volume of files in a single job although submission time is still long due to repeated (blocking) polls of the catalog.
- 2 blocks were submitted concurrently on the RAL, SARA and IN2P3 channels.
- All of these files transfered successfully. During this period transfer rates of ~90MB/s were seen out from CERN.
- The attempt to transfer DC04/v1 data failed due to Configuration issues (data is not on LCG area at CERN).




Friday, Oct 7th



LastDay Bandwith for FTS protocol by Channel






□ CERH_Castor -> GRIDKA_dCache
□ CERH_Castor -> III2P3_HPSS
□ CERH_Castor -> NIKHEF_dCache
□ CERH_Castor -> PIC_Castor
□ CERH_Castor -> RAL_dCache
□ Total Files











- LHCb SC3 Service Phase activities have started
- Final debug of the Bulk Transfer Tools (TransferAgent).
- Good performance observed.
- Good response from sites.
- Ready for massive data movements.
- Need to test the long term stability.

